То:	Town of Lincoln, Vermont	From:	Brian Cote, PE, CFM
			Osman Pekin
			Elizabeth Richards
Company:		SLR International Corporation	
cc:	Addison County Regional Planning	Date:	September 18, 2023
	Commission	Project No.	146.13928.00008
RE: Rive	r Road Stabilization		

1.0 Introduction

The following narrative has been prepared to document findings and data collection, and to provide conceptual alternatives to address roadway stability along the River Road project site located in Lincoln, Vermont. This memorandum summarizes findings and discusses site constraints, presents conceptual alternatives, and recommends next steps for the Town to consider moving forward.

The New Haven River travels through a narrow valley and is located directly adjacent to the embankment of River Road at the project site (Figure 1). The River Road embankment has historically been armored with large riprap to resist erosion that has occurred within the project reach. Maintaining the riprap slope has been challenging given the direct flow impingement, the steepness and height of the embankment, and dynamic nature of the New Haven River. There is also concern with the stability of the tall, steep slope on the north side of River Road may also be actively destabilizing this section of the roadway.



Figure A: River Road Project Area

A project kickoff meeting with the Town of Lincoln, the Addison County Regional Planning Commission, and SLR was conducted on March 29, 2023. During the meeting, the challenges that the Town has experienced along this section of River Road were discussed along with their thoughts of what may be causing some of the issues. Concern that the steep slope between River Road and Forge Hill Road was causing instability in the roadway was discussed, as well as damages that this site has faced during past flooding on the New Haven River. A nearby site that the Town recently repaired was also toured after the kickoff meeting. Notes that were taken at the meeting are attached (Appendix A).

2.0 Existing Conditions

The New Haven River channel through the project area is currently confined by the River Road roadway embankment to the north and a disconnected floodplain and flood chute to the south. Additionally, the roadway is located on the outside of a meander bend in the river, and a gravel bar is building on the inside of the bend. These conditions contribute to the instability and erosion risk of the River Road embankment.

The roadway embankment is currently lined with riprap along an approximately 250-foot section of the New Haven River within the project area. River Road is showing signs of settlement and movement (i.e., longitudinal cracking of roadway surface and leaning guardrail). Road drainage is causing localized rill erosion on the south side of the roadway where stormwater runoff leaves the roadway surface and collects before flowing down the steep slope to the river. Additionally, the steep slope between Forge Hill Road and River Road is showing signs of movement and instability that may be applying pressure to the roadway in the project area as well. The New Haven River flows directly adjacent to the roadway embankment. The alignment is causing direct flow impingement on the base of the embankment contributing to the slope instability. To address the instability, a stacked riprap wall with steep armored upper bank has been implemented along this section of River Road within the limited space available between the roadway and river. Vegetation along the roadway embankment that has not been eroded away is limited to grasses and small shrubs within the section that is most vulnerable to erosion risks.

A gravel bar is building on the inside of the bend opposite the roadway to the south, adding to the pressure along the roadway embankment. Additionally, the forested floodplain and flood chute located to the south of channel appears to be largely disconnected from the river. When floods take place on the New Haven River in this location, most of the water is contained in the channel leading to increased erosion risk.

A site walk was conducted on June 14, 2023 by SLR staff to review conditions, collect field data, and document existing site constraints. Field notes taken during the site walk are attached (Appendix B). During the site walk, the erosion risk level was assessed along River Road within the project area (see plan sheets EX1 – EX4 of the plan set attached in Appendix C). Existing conditions and site features such as storm drainage, culverts, existing erosion, potential natural resources, and topographic data were collected and mapped during the site walk. Additional information and details regarding the existing conditions at the project site is provided in the subsections below.

2.1 Road Embankment

The road embankment through the project site is located on the outside of a bend in the New Haven River and is susceptible to erosion at the toe of slope that sits at the river's edge. The embankment is approximately 20 feet tall and is over-steepened with an average slope of 1V:1.5H. Vegetation is sparse on the steepest portion of the embankment where large riprap has been placed, consisting of grasses and small shrubs mostly at the top of the embankment. The embankment at each end of the project area appears more stable where there is less impingement and more vegetation to protect against erosion.

A metal-beam guiderail exists at the edge of the roadway along the length of the embankment within the project area. Sections of the guiderail are leaning towards the river indicating that the slope is unstable and likely moving. There is also cracking along the direction of travel in the road that is visible in the pavement of the roadway surface that also may be an indication of the road embankments instability. There are several small earth berms at the top of the slope just behind the guiderail that concentrate runoff flowing off the roadway surface. The berms may be the result of buildup of winter road sand and eroded sediment.

2.2 Fluvial Geomorphology

The New Haven River is a steep, high energy, riffle-pool channel with areas dominated by bedrock and cobble. The river channel has cut down (i.e., incised) in the project area leading to disconnected floodplains and over-steepened banks along River Road. This setting has led to high erosion risk and repeat damages along the road and ongoing damages to the road embankment.

A disconnected flood chute exists at the upstream end of the project site that is directing more flow towards the damaged road embankment. If reconnected, this chute could move some water away from the road during flood and reduce risk to the road.

Active sediment bar building is taking place at the upstream end of the project site that is leading to increased meandering and bank / road embankment erosion.

The measured bankfull channel width is 49 feet and the bankfull depth is 5.5 feet.

2.3 Hydrology

The River Road project site is approximately 10 miles downstream of the headwaters of the New Haven River watershed that originates on the western slopes of the Green Mountains. The New Haven River at the project site has a drainage area of approximately 43.5 square miles and is part of the Lake Champlain Otter-Lewis sub-basin. The majority of the basin draining to this point is mountainous with an average stream slope of approximately 5%. The local channel slope of approximately 1.2%. The basin is primarily forested with a small percentage of residential and agricultural land uses mixed in. The narrow, elongated watershed shape and existing land uses limit peak flow rates to this point, however, the steep sloped watershed indicates that a flashy characteristic would be anticipated at this location in the watershed, where peak flows pick up then recede relatively quickly during flood events.

Recurren	ce Interval	Peak Flow Rate	Unit Peak Flow Rate		
Year	% Annual Chance	(CFS)	(CSM)		
2-year	50.0%	1,540	35.4		
5-year	20.0%	2,370	54.5		
10-year	10.0%	3,010	69.2		
25-year	4.0%	3,950	90.8		
50-year	2.0%	4,750	109.2		
100-year	1.0%	5,610	129.0		
500-year	0.2%	7,980	183.4		
CFS – cubic feet per second					
CSM – cubic feet per second per square mile					

Table 1: Peak Flow Rates – USGS StreamSTATs

2.4 Storm Drainage

Storm drainage within the project area generally consists of roadside swales and cross culverts that are often used in similar settings. The roadway surface is generally cross sloped to drain towards the top of the road embankment. When in the field, localized rill erosion was observed where runoff flowed off the road surface and concentrated against earth berms, before flowing down the embankment at gaps between berms. The runoff from the roadway surface appeared

to be causing some issues with erosion and stability of the shoulder at the top of the road embankment.

At the eastern end of the project area, there is a watercourse that drains towards River Road from the north. An actively eroding gully was observed where the watercourse travels down the steep slope from Forge Hill Road. Flow from the watercourse passes under River Road in a 60-inch diameter corrugated metal pipe (CMP) culvert that appeared to be in fair to good condition. Riprap armoring has been placed at both the inlet and outlet of the culvert to protect against erosion. The inlet appeared to be stable, however some signs of erosion were observed at the outlet.

Along the northern edge of the roadway, there is a drainage swale that directs runoff to a series of three 18-inch diameter CMP cross culverts. The three culverts appear to primarily convey stormwater draining towards the road from the steep slope between River Road and Forge Hill Road, and the roadway surface itself is generally cross sloped towards the river to the south along this portion of River Road. As you move westerly through the project area, the steep slope leaves limited space for a drainage swale. Rill erosion was observed at the ends of all three 18-inch culverts where runoff flows around the end of the culverts and down the road embankment.

A drop inlet structure with an 18-inch diameter CMP culvert was observed at the western-most end of the project area. Erosion was observed at the outlet of the 18-inch CMP culvert that was projecting from the road embankment and several feet above grade. In this portion of the project area, the road surface was cross-sloped towards the north side of the roadway to a swale. The swale extends to the intersection between Forge Hill Road and River Road along the base of the slope between the two roads. A notable observation while in the field was that in this portion of the project area, the guiderail was not leaning towards the river, as it does through the remainder of the project area.

2.5 Utilities

There were no overhead utility lines or utility poles observed within the project area during the site visit. There were no signs of underground utilities observed within the project area also.

2.6 Natural Resources

There are several areas along the roadway (typically surrounding existing culverts) that may be designated wetlands. Additionally, there is a disconnected flood chute across the river that may be designated wetland.

Indicators of Ordinary High Water (OHW) along the New Haven River were surveyed while in the field. The survey points were used to approximate the limits of OHW along the river as shown on the plans. Additional field assessment will be required to finalize the OHW limits as design progresses.

3.0 SLOPE STABILITY

SLR's geotechnical team performed a limited review of the site conditions based on aerial images, photographs, and available geologic and topographic information. There are no available borings to indicate likely subsurface materials or groundwater conditions. The initial



assessment aimed to postulate likely scenarios and corresponding investigative approaches, which were then narrowed down to the investigation plan currently proposed (see Section 9.3). Various investigative methods that were considered included geophysics, borings, Cone Penetration Testing, and slope movement monitoring options using inclinometers or Time Domain Reflectometry. Also, various boring locations and depths were considered.

Data provided on regional geology map was reviewed and indicates that there is underlying hard rock at the site (USGS Bedrock Geologic Map of Vermont (Ratcliffe et al., 2011)). This site is located approximately where the Forestdale Formation (light blue band) crosses the New Haven River (Figure B).

The regional geologic maps are a good source of data, however do not provide information on local variability. For example, the upper slope along Forge Hill Road may have been created by infilling a historic flow channel, in which case the materials within a potential slide zone could consist of soil, which is more susceptible to sliding than bedrock. Also, groundwater conditions, which are currently unknown, could influence slope stability.





Figure B: Regional Geological Map

If hard rock is encountered within reasonably shallow depths in boring explorations, that would preclude the likelihood of deep-seated global failure. There could still be localized shallow and/or narrow weak zones, but geometrically, those would not lead to a global slope failure. The likelihood of rock being encountered during boring investigation is reasonably high given that occasional rock outcrops were observed at the site and considering the relatively steep gradient



that this slope has endured. Based on this interpretation, an investigation plan that can be considered reasonable while providing required data needed to analyze the slope stability has been developed as outlined in Section 9.3 below.

Evidence was observed in the field that indicates that the lower portion of the slope between River Road and New Haven River is experiencing slope movement. This is likely triggered by scouring along the northeasterly bank of the river within its southwest-facing bend. It is less clear if potential slope instability extends further uphill, between River Road and Forge Hill Road. If there is any potential instability in the uphill portion of the slope, it is not clear if it has a shallow slide risk or a deep-seated slide (Figure C). The orange line depicts a slope toe failure, which is reasonably substantiated by observations in the field. The green line (i.e. – shallow slide) or red (i.e. – deep-seated slide) are unknown scenarios that involve the larger slope.



Figure C: Schematic of Various Slope Failure Scenarios (Source: SLR)

4.0 ALTERNATIVES ANALYSIS – ROAD EMBANKMENT

The following sections describe a number of alternatives that could be implemented within the project site to improve the stability of the road embankment. Several of the alternatives would be implemented along the road embankment that focus on slope stability, while others would primarily be related to increasing resiliency during flooding.

4.1 Alternative 1 - No Action

This alternative would leave the failing existing embankment in place. This alternative would minimize construction costs; however, it would not reduce the risk of damage to the roadway due to bank erosion, or improve water quality and habitat by stabilizing the channel bank. Although there wouldn't be construction costs for implementation associated with this alternative, the current need for maintenance and relatively frequent repairs would remain along with their associated costs. This alternative is not recommended due to the high risk associated with the roadway embankment failing completely since the existing armoring has been destabilized. The shifting of the guard rail and settling of the road embankment suggest that road failure could take place in the next large flood indicating that work is needed to reduce risks.

Table 2: Alternative Matrix – No Action

Reduce flood and erosion risks to road	Stabilize river bank to improve water quality and habitat	Minimize construction costs	Minimize future maintenance needs	Total Score
1	1	3	1	6
Scoring based on 0 – 3 scale, 0 = not applicable, 1 = lowest goal achievement, 3 = highest goal achievement				

Although there are no construction costs associated with the no action alternative, costs associated with needed repairs and frequent maintenance would be anticipated.



Figure D: Existing Roadway Embankment

4.2 Alternative 2 – Repair Stone Armoring

This alternative consists of recovering stone that has fallen into the river and placing it back on the embankment. Portions of the existing armoring that have shifted and destabilized would need adjustment. Additional stone armoring would also be required.

It is anticipated that permitting for this alternative would be straight forward since regulators would likely consider this to be maintenance with minimal temporary disturbance within ordinary high water (OHW) during construction. Construction would likely require closing at least one lane of traffic and lowering the embankment to reach the base of the slope. Impacts and clearing of vegetation would be limited to areas where armoring exists. Tree clearing would be required only if the extent of the existing armoring is extended up- and downstream to protect more of the roadway embankment.

This alternative would reduce flood and erosion risks to the road and would minimize construction costs relative to other alternatives. However, this alternative would not minimize future maintenance needs or naturalize the riverbank. This alternative is not recommended since this approach typically requires frequent maintenance and repairs of failing stone every 5 to 10 years following floods and heavy ice out events.

Reduce flood and erosion risks to road	Stabilize river bank to improve water quality and habitat	Minimize construction costs	Minimize future maintenance needs	Total Score
2	2	3	1	8
Scoring based on 0 – 3 scale, 0 = not applicable, 1 = lowest goal achievement, 3 = highest goal achievement				

Table 3:	Alternative Matrix – Repair Stone Armoring	1
Table 5.	Alternative matrix – Repair Otorie Armoning	J

This alternative is estimated to cost approximately \$800 per linear foot for implementation. Based on the extents shown on the conceptual plan, this alternative would cost roughly \$800,000 to construct. Note that this cost is based on 30% design, using a conservative approach, the scope and extents of the project would be refined as design advances. Although the construction cost is less than other alternatives presented, costs associated with repairs and maintenance costs would be more frequent. In addition, the rough cost provided for this alternative assumes that the full extent of the embankment stabilization area shown on the conceptual plan would be repaired, although a lesser extent likely requires immediate attention.



BOULDER REVETMENT KEY NOTES:

- EMBED THE STONE A MINIMUM OF 4 FEET INTO THE STREAM BED AND 8 FEET INTO THE STREAM BANK TO KEY.
- FINISHED ELEVATION OF THE STONES AS SHOWN ON CROSS SECTIONS AND GRADING PLAN.

Figure E: Typical Stone Armored Slope

4.3 Alternative 3 – Rebuild Stone Armoring with Pinning

This alternative consists of dismantling the existing stone armoring on the roadway embankment and rebuilding the slope protection with a stacked stone wall on the lower slope and sloped armoring on the upper slope. The height of the stacked stone wall would be built to a point where the upper slope can attain a reasonable slope of 1.5H:1V to 2H:1V. Vegetation on the upper slope would be reestablished using joint plantings and live stakes. The vegetation would help increase habitat and help stabilize the slope by reducing surface erosion caused by stormwater runoff draining off the roadway surface.

The stacked stone wall would be keyed below the channel bed to protect against scouring, and large stone boulders used to create the wall would be pinned together using rebar dowels and grouting. If shallow bedrock, the base of the stacked stone wall would be pinned to the bedrock.

The stacked lower portion of the application can help maintain the bankfull width available to the channel, whereas sloped armoring would encroach into the channel.

It is anticipated that permitting for this alternative would be straight forward, since regulators would largely consider this to be maintenance, although temporary disturbance within OHW during construction would increase to allow keying of the stacked stone wall and for water control. A similar design was recently permitted downstream in Bristol. Construction would likely require closing of at least one lane of traffic and would require lowering the road embankment to reach the base of the slope to create the key and install pins. Impacts would be limited to areas where armoring exists, and tree clearing would be limited to the up- and downstream extents of the application in areas where stone armor protection is expanded along the roadway embankment.

This alternative would reduce flood and erosion risks to the road, minimize future maintenance needs and minimize construction costs but would not naturalize the riverbed. Comparatively, construction costs for this alternative would be more than Alternative 2, however maintenance costs would decrease since this approach would be more durable than stone armoring without the pinning.

Reduce flood and erosion risks to road	Stabilize river bank to improve water quality and habitat	Minimize construction costs	Minimize future maintenance needs	Total Score
3	2	2	3	10
Scoring based on $0 - 3$ scale, $0 =$ not applicable, $1 =$ low goal achievement, $3 =$ high goal achievement				

 Table 4:
 Alternative Matrix – Rebuild Stone Armoring with Pinning

This alternative is estimated to cost approximately \$1,500 per linear foot for implementation. Based on the extents shown on the conceptual plan, this alternative would cost approximately \$1,500,000 to construct. Note that this cost is based on 30% design, using a conservative approach, the scope and extents of the project would be refined as design advances.



Figure F: Typical Stacked Stone Wall with Pinning

4.4 Alternative 4 – Concrete Flood Wall

This alternative would consist of constructing a concrete flood wall at the lower portion of the embankment, with sloped stone armoring placed above the flood wall. This alternative would require closing the roadway during construction to allow for the excavation required to construct the foundation and wall. The construction period would also be longer than Alternatives 2 and 3. In addition, the aesthetics of this alternative may be less desirable in the New Haven River setting that is more natural with stone and bedrock. Similar to Alternative 3, this approach can help maintain the bankfull width of the channel.

Although this alternative would be more durable than other alternatives using only stone armoring, the cost to implement would be comparatively much higher. Maintenance of a concrete wall, although potentially less frequent, would potentially be more expensive as well, especially given difficulties with access to the wall placed along the river's edge.

It is anticipated that permitting for this alternative would be more challenging, as regulators would consider permanent impacts as well as temporary disturbances during construction. Using this approach over less costly and impactful alternatives may be difficult to justify to regulators. Temporary disturbances within OHW during construction would be high due to extensive excavations and water control in the river. Required tree and vegetation clearing would likely be greater than other alternatives due to excavation requirements and potentially extending the portion of roadway embankment that is protected by the flood wall.

This alternative would reduce flood and erosion risks to the road and minimize future maintenance needs but would not minimize construction costs or provide a more natural riverbank.

Reduce flood and erosion risks to road	Stabilize river bank to improve water quality and habitat	Minimize construction costs	Minimize future maintenance needs	Total Score
3	1	1	3	8
Scoring based on 0 – 3 scale, 0 = not applicable, 1 = low goal achievement, 3 = high goal achievement				

Table 5:	Alternative Matrix -	- Concrete Flood Wall	l with Armored Upper Bank

This alternative is estimated to cost approximately \$2,500 per linear foot for implementation. Based on the extents shown on the conceptual plan, this alternative would cost approximately \$2,500,000 to construct. Note that this cost is based on 30% design, using a conservative approach, the scope and extents of the project would be refined as design advances.



Figure G: Typical Concrete Flood Wall Detail



Figure H: Concrete Flood Wall Example



Figure I: Concrete Flood Wall Example

4.5 Alternative 5 – Mechanically Stabilized Earth Wall

This alternative would consist of constructing a Mechanically Stabilized Earth (MSE) wall along the lower portion of the roadway embankment. Like Alternative 4, sloped stone armoring would be placed above the wall on a more gradual slope up to the roadway surface. This alternative would likely require closing the roadway during construction to allow for the excavation required to construct the MSE wall, the construction period would also be comparatively longer than other alternatives, and the aesthetics of this alternative may be less desirable in the New Haven River setting. The MSE wall approach used in Alternative 5 would help maintain the bankfull width of the channel.

Although this alternative would be more durable than other alternatives using only stone armoring or just a gravity wall, the cost to implement would be higher, and potentially more costly than a flood wall. Maintenance requirements of a MES wall would be similar to a concrete flood wall with similar associated cost.

A variation of this alternative would be to use gabion baskets rather than concrete panels to create the wall. A geosynthetic material would be attached to the gabions to mechanically stabilize the lower wall portion. Gabion use would result in a less durable wall portion, however typically is less costly than concrete. The aesthetics of gabion baskets are often less desirable as well.

It is anticipated that permitting for this alternative would be more challenging, as regulators would consider permanent impacts as well as temporary disturbances during construction. Using this approach over less costly and impactful alternatives may be difficult to justify to regulators. Temporary disturbances within OHW during construction would be relatively high due to extensive excavation and water control. Required tree and vegetation clearing would likely be greater than other alternatives due to excavation requirements and potentially extending the portion of roadway embankment that is protected by the flood wall.

This alternative would reduce flood erosion risk to the road but would not minimize construction costs or naturalize the riverbank.

Reduce flood and erosion risks to road	Stabilize river bank to improve water quality and habitat	Minimize construction costs	Minimize future maintenance needs	Total Score
3	1	1	3	8
Scoring based on $0 - 3$ scale, $0 = not$ applicable, $1 = lowest goal achievement$, $3 = highest goal achievement$				

Table 6: Alternative Matrix – Concrete Flood Wall with Armored Upper Bank

This alternative is estimated to cost approximately \$1,200 per linear foot for implementation. Based on the extents shown on the conceptual plan, this alternative would cost approximately \$1,200,000 to construct. Note that this cost is based on 30% design, using a conservative approach, the scope and extents of the project would be refined as design advances.



Figure J: Typical Mechanically Stabilized Earth Wall Design Detail



Figure K: Typical Mechanically Stabilized Earth Wall Design Schematic



Figure L: Mechanically Stabilized Earth Wall Example

4.6 Alternatives Matrix

Alternative ID	Reduce flood and erosion risks to road	Stabilize river bank to improve water quality and habitat	Minimize construction costs	Minimize future maintenance needs	Total Score	Approximate Construction Cost
1 - No Action	1	1	3	1	6	n/a
2 - Repair Stone Armoring	2	2	3	1	8	\$800,000
3 - Rebuild Stone Armoring with Pinning	3	2	2	3	10	\$1,500,000
4 - Concrete Flood Wall	3	1	1	3	8	\$2,500,000
5 - MSE Wall	3	1	1	3	8	\$1,200,000
Scoring based on 0 – 3 scale, 0 = not applicable, 1 = lowest goal achievement, 3 = highest goal achievement						

5.0 ALTERNATIVES ANALYSIS – RIVER CHANNEL

The following alternatives related to the river channel and floodplain could be implemented in addition to the selected road stabilization alternative to reduce erosion potential.

5.1 Alternative RC1 – Flood Chute Reconnection

Flood chute reconnection consists of removing material at the entrance of an existing flood chute so that it can be accessed during flood events. Currently, the flood chute that exists on the south side of the New Haven River appears to be largely disconnected from the river. During flooding, the disconnected entrance prevents floodwaters from accessing the chute. This alternative would consider lowering the existing grade at the chute entrance to allow floodwater to access the flood chute during a flood of a desired size or frequency. An evaluation of the river hydraulics during flooding would be required to determine at what flood level the chute would activate. Reconnecting the flood chute will allow a portion of the flow to enter the chute and bypass a portion of the main channel that flows along the road embankment, and therefore reduce pressure on the River Road embankment within the project site that is most susceptible to erosion. This approach has been implemented at numerous sites in Vermont in similar settings with similar constraints and conditions.



Figure M: Typical Flood Chute Reconnection Detail

5.2 Alternative RC2 – Channel Bed Armoring & Raising

This alternative consists of armoring the channel bed with large diameter stone armoring that will help reduce the risk of channel downcutting. When the channel bed is downcutting as observed at this site, the risk of undermining and destabilizing the armored slope increases. In addition, downcutting increases incision of the channel and disconnects the river from the adjacent floodplain during flood events.

Where feasible, raising the channel bed in conjunction with the armoring can help reduce incision and therefore reconnect the river to its floodplain. Allowing the river to access its floodplain during flooding helps spread flow and reduce velocity that is associated with stream power and erosion potential. Channel bed raising would also effectively increase the bankfull width available within the channel, while decreasing the overall height of the road embankment that would help with stability.



Channel bed armoring would be achieved by removing native river sediment and replacing it with a layer of stone riprap. The stone riprap would then be covered with native river sediment washed down into the large voids of the riprap. Choking the voids and establishing a layer of native sediment over the large riprap will prevent underflow (i.e., where flow drops into the voids of the riprap, rather than remain at the surface), maintain natural instream habitat in the channel, and allow the surface layer to erode and deposit naturally. Where bed raising is implemented, the top of the finished channel bed armoring would be set above existing if feasible. Additional evaluation would be required to determine if raising the channel bed would be feasible at this site. Both channel bed armoring and raising have been successfully permitted and constructed at numerous sites along Vermont roadways that have similar challenges found at the River Road project site.



Figure N: Typical Channel Bed Armoring Detail

5.3 Alternative RC3 – Floodplain Reconnection

Floodplain reconnection consists of lowering existing grades adjacent to a river that would allow floodwaters access to the floodplain during an event of desired size or frequency. This alternative is often implemented in areas where the natural floodplain has historically been filled or in areas where floodplains have been disconnected from rivers where downcutting or incision has occurred. Reconnecting a river to a floodplain is beneficial because it allows floodwaters to spread and therefore velocity decreases along with related erosion hazards and risks. If the floodplain reconnection is large enough, another benefit would be a reduction in flood depth and water surface elevation during flooding due to providing additional storage volume on the floodplain.

A potential drawback to floodplain reconnection is clearing of vegetation and trees during construction. The clearing can sometimes create an adverse environmental impact by removing riparian buffer and shading of the river that trees provide. This impact can be offset by implementing a planting plan to restore the riparian buffer. Extensive planting plans for large floodplain reconnection projects can add a considerable amount of cost when implementing a floodplain reconnection project.





Figure O: Typical Floodplain Reconnection Detail

6.0 ALTERNATIVES ANALYSIS – DRAINAGE

The following alternatives related to drainage could be implemented in addition to the selected road stabilization alternative to reduce erosion potential.

6.1 Alternative D1 – Road Profile and Crown Adjustment

This alternative consists of adjusting the roadway profile or crown, or a combination of both, in order to direct runoff to a more suitable and stable location where the stormwater can be safely conveyed to the discharge point. The benefit of adjusting the road profile or crown would be to redirect stormwater away from the top of road embankment where localized erosion was observed. Changes to the profile and crown may be constrained by the limited space between the top of road embankment and steep slope on the north side of River Road. In addition, changes to the profile or crown would need to meet roadway design standards to maintain safe travel conditions.

6.2 Alternative D2 – Swale Reconnection

Swale reconnection would consist of reshaping the roadside swale along the northern side of River Road and conveying to cross culverts. The limited space available between the roadway edge and the steep slope on the north side of River Road may limit swale reconnection.

6.3 Alternative D3 – Flow Distribution

Flow distribution consists of evaluating how much stormwater runoff is draining to the existing cross culverts to determine if additional cross culverts should be installed to better distribute the runoff. Calculations would be performed to determine if the size of existing culverts are adequate or if they need to be upsized.

6.4 Alternative D4 – Stabilized Flow Paths

This alternative consists of evaluating existing and proposed flow paths created as part of drainage improvements to ensure that they are stable and not susceptible to erosion. New and existing swales would be stabilized using vegetation if site conditions and anticipated flow velocities allow, or be protected with stone riprap. Inlets and outlets would be protected with stone armoring to stabilize the areas along the roadway and embankment. Where stormwater sheet flows off the roadway surface, shoulders would be shaped to maintain sheet flow and stabilized with vegetation. Stabilizing flow paths would work in conjunction with stabilization measures proposed along the road embankment.

7.0 Permitting Requirements

The regulatory permits that will likely be required for this project include:

- Stream Alteration Permit Vermont Department of Environmental Conservation
- VT General Permit U.S. Army Corps of Engineers
- Local Zoning Permit Town of Lincoln

In addition, the following permits may be required depending on the size and scope of the alternative(s) selected:

- o Construction Stormwater Permit Vermont Department of Environmental Conservation
- Wetland Permit Vermont Department of Environmental Conservation

In addition, the proposed design of any drainage improvements would need to comply with the Vermont Municipal Roads General Permit (MRGP) requirements and standards.

8.0 Recommendations

The recommended alternative that the Town should consider exploring further in order to reduce erosion risks and increase stability of the River Road embankment at the project site is Alternative 3, Rebuild Stone Armoring with Pinning. This alternative balances construction costs and constructability with maintenance requirements, associated costs, and durability. Alternative 3 also minimizes temporary impacts during construction and therefore simplifies the permitting process compared to other alternatives.

In addition, it is recommended that the Town explore flood chute reconnection (RC1) and channel bed armoring (RC2). Implementation of these alternatives would help reduce erosion pressure on the roadway embankment during flood events and reduce impacts to the river channel with maintenance requirements.

Implementation of drainage improvements that will help reduce localized rill erosion at the top of the roadway embankment is also recommended (D1, D2, D3, and D4). Drainage improvements would include evaluation of road surface drainage by potentially modifying the crown, evaluating



the capacity of culverts, adding culverts if needed, evaluating improvements to the roadside swale, and providing efficient culvert inlets and protected outlets. The design of improvements should promote distributed sheet flow off the roadway and down the embankment, rather than concentrated flow that increases the risk of erosion. Sheet flow through vegetation will also help filter stormwater. The opportunity to adjust the road surface to direct stormwater runoff to an improved swale along the north side of the road should also be explored. The roadway embankment appears to be more stable and has less rill erosion at the top of the bank in areas where the road surface sheds runoff to a swale at the northern edge of the roadway. This alternative may be limited by roadway profile requirements and the space available along the northern roadway edge for a swale.

The recommended alternatives have been shown on the attached conceptual design sketch with typical details (Sheets PR-1 and PR-2 of Appendix C).

9.0 Next Steps

The following next steps are recommended to advance the project.

9.1 Topographic and Boundary Survey

Conduct a more detailed survey of the project site to collect topographic data and the location of site features. The survey may need to include a boundary retracement to establish the Right-of-Way and adjacent parcels to determine temporary or permanent easement requirements. The cost to perform the topographic survey at the site is estimated to be approximately \$10,000. If a boundary survey is required to establish the right-of-way and property boundaries, an additional \$8,000 is estimated.

9.2 Wetland and Natural Resource Delineation

Conduct a wetland delineation and assessment to confirm if wetlands exist in the areas identified during this initial assessment and what their quality is. If wetlands are present, the formal delineation and assessment will guide design and permitting. The delineation of Ordinary High Water (OHW) should also be confirmed. Additional measurements can be taken to confirm bankfull dimensions while walking along the river channel. The cost to perform the wetland delineation at the site and provide the information required to guide design and permitting is estimated to be approximately \$4,000.

9.3 Deep Soil Investigation and Geotechnical Analysis

The recommended method for investigating subsurface conditions is to conduct borings and install inclinometers and monitoring wells at each borehole location to monitor ground movement and groundwater levels. River Road traverses the subject slope at a lower elevation, along New Haven River, while Forge Hill Road is along the top of the subject slope. The elevation difference between the river and the lower road is about 20 to 25 feet and the elevation difference between the lower and the upper road is about 70 to 75 feet. The approximate 100-foot-tall slope has a gradient of about 2H:1V or steeper locally.

Two borings are proposed – one at the south edge of River Road closer to the river (Boring SB-1), and the other at the north edge of River Road (Boring SB-2), at the approximate locations depicted in Figure P. Each borehole will be fitted with a slope inclinometer casing and a small-diameter groundwater observation well. These borings will be drilled to approximately 30 feet depth each, or to refusal if encountered at a shallower depth.

An inclinometer at Boring SB-1 is expected to pick up ground movements from the localized toe failure (Figure C). An inclinometer at SB-2 is expected to provide information on whether or not ground movements are occurring that connect to the upper slope (Figure C). Note that the exploration plan may need to be modified based on conditions encountered during drilling.



Figure P: Site Layout and Proposed Boring Locations

The estimated cost for this investigation is approximately \$25,000. This would include the borings, sampling, laboratory testing, inclinometer and observation well installations, monitoring of inclinometers and observation wells for three months, slope stability analysis, and preparation of a geotechnical report with recommendations for design of stabilization measures as applicable.

Topographic Survey	Boundary Survey	Wetland Assessment	Subsurface Exploration & Geotechnical Analysis	Total
\$10,000	\$8,000	\$5,000	\$25,000	\$48,000

Table 7: Next Steps Summary Table

10.0 REFERENCES

Ratcliffe, N. M., R. S. Stanley, M. H. Gale, P. J. Thompson, and G. J. Walsh, 2011. Bedrock Geologic Map of Vermont. U.S. Geological Survey Scientific Investigations Map 3184, 3 sheets, scale 1:100,000.

APPENDIX A – KICKOFF MEETING NOTES





SLRC SHEET NO. _____ OF ____ SCALE global environmental and DATE CALCULATED BY advisory solutions DATE CHECKED BY D Reach out to VEM - D check on potentral elisibility Andrew to BRIC or HIMAP (Pre-idisaster mitigation) D 1938 - D niprap in 1960 photo D dredged all the way to Bristol D 5 feet moved out into viver at nearly site - D Davan Borg - helped w/ other site, get on pand o 4/5 grave bar - town was mining to use - D road washed out for 1 moth the - 1998 L & Both Buidges washed out 1998 - D TAC nel 3 °C weds of each month - O Sept 20th -> funding hard deadline Sept 30 1/2 - Notity Town when in Field Lo pall off end: 11:00 Am

APPENDIX B – FIELD WORK NOTES

River Rd - Lincoln Bunc June 14 0023 RKS Disside: Bisonom partly cloudy - +600F Flow's below gig. -DA-Low - heavy veg, flood bench no impingment, large trees gravel bar -DB - moderate some lard trees - ver thinning, bar building starts on opposite bank begin impiggerent, aracles in 58 travel lane, no Flood bench trainage off L.P. in Sung Pulloff causing fill crossion -PC - grass, Knot wed, per-ici Mit some armoning no fibed some armoning, no fibed sta bunch hav building on sh apprise side, outside but & no should in minor anaching inter the

-C - con't - still some slope, channel disconnet from bench an aposite 212 Side narrow chunt viffle S-8 - reed drainager vill erosion@ 8-2 top of slope - better / toe argumented, Steep 2 3 -D-Hish permin q on 2 1 - steep upper back, no veguipper 2-0 only Steep armor & top, distaktions Signs of everyon disconnect 8-1 From Rued bandy 2 3 vill exosion on upper from road drainage The second second - araching langitudional in both travel lanes - bank arosion on appoite --narrow anannel, riffle section - direct impirgment, bur building in opposite --E - High to median - Towerish due to river - histor for to steepvess the - montrolled number, Slope fuilts -- 10 crown, HP on outsile opposite with bank all runoff of 6

E-con+ - ver cover on bank, saplings to med trees, 50055, purmines · longituding cracking in road - Perpendicular maching patches at and grossings -Hist, armoning @ toe - viver becomes parrathel - deeper/pools in viver

moderate / medium -F- drainage to other side W difeh / crown HP on viver Side - less runoff and sloke - Still Steep, some shoulder - vailing not leaning - river parvallel - ves, larger trees -armonias historice toe - begin bar building or road side

Rite in the Rais

- G-Low - Irainage to other side of word, liteling - more shoulder, less steep - viver moves away, benaly & bay building on read site - Slope / wad embanement not as fall - drop structure w/ to control runge - apposite slope is more gentle not as tall Wet seekin C D (MI Signal OST Pad^ -0.7' Dist 5 0.0' (put ors) ROW 4. D' -2.5' 7.5' -3.5 **C**3 14.51 -2.0' 21.0' -0.71 27.0 LOW -0.D1 C2 K-E BF width = 49 fb -BF. depth= +5.5' (2.0' ghavy TW) + - Oid from Row put--N- rod reading below WSEL



RIVER ROAD STABILIZATION PROJECT TOWN OF LINCOLN, VERMONT

0 25 5 Feet 1 in = 50 feet

Feild Notes -06/14/2023

BWC RKS 1.pg1.

SLR^O 1 SOUTH MAIN ST WATERBURY, VT 05676 802.882.8335



SHEET 3 - EXISTING CONDITIONS

RIVER ROAD STABILIZATION PROJECT TOWN OF LINCOLN, VERMONT

Feet 1 in = 50 feet





SHEET 4 - EXISTING CONDITIONS

RIVER ROAD STABILIZATION PROJECT TOWN OF LINCOLN, VERMONT

Feet 1 in = 50 feet

N



SHEET 5 - EXISTING CONDITIONS

RIVER ROAD STABILIZATION PROJECT TOWN OF LINCOLN, VERMONT

1 in = 50 feet



SHEET 6 - EXISTING CONDITIONS

RIVER ROAD STABILIZATION PROJECT TOWN OF LINCOLN, VERMONT

Fee 1 in = 50 feet



APPENDIX C – CONCEPTUAL DESIGN PLANS

RIVER ROAD STABILIZATION

RIVER ROAD LINCOLN, VERMONT

> CONCEPT DESIGN AUGUST 31, 2023



PROJECT SITE VICINITY MAP:



PREPARED BY:

₩SLR

1 SOUTH MAIN STREET WATERBURY, VT 05676 802.882.8335 SLRCONSULTING.COM





SCALE 1" = 2000'

PREPARED FOR:

ADDISON COUNTY REGIONAL PLANNING COMMISSION 14 SEMINARY STREET MIDDLEBURY, VERMONT 05753

LIST OF DRAWINGS:

О.	NAME	TITLE
1		TITLE SHEET
2	OV-1	OVERVIEW MAP
3	EX-1	EXISTING CONDITIONS
4	EX-2	EXISTING CONDITIONS
5	EX-3	EXISTING CONDITIONS
6	EX-4	EXISTING CONDITIONS
7	XS-1	EXISTING TYPICAL SECTION
В	PR-1	PROPOSED CONDITIONS
9	PR-2	PROPOSED TYPICAL SECTION



SHEET OV-1: OVERVIEW MAP

RIVER ROAD STABILIZATION TOWN OF LINCOLN, VT







SHEET EX-1: EXISTING CONDITIONS

RIVER ROAD STABILIZATION TOWN OF LINCOLN, VT

0 5 10 20 30 40 50 Feet 1 in = 50 feet AUGUST 31, 2023







SHEET EX-2: EXISTING CONDITIONS

RIVER ROAD STABILIZATION TOWN OF LINCOLN, VT

0 5 10 20 30 40 50 Feet 1 in = 50 feetAUGUST 31, 2023





SHEET EX-3: EXISTING CONDITIONS

RIVER ROAD STABILIZATION TOWN OF LINCOLN, VT

0 5 10 20 30 40 50 Feet 1 in = 50 feet AUGUST 31, 2023





SHEET EX-4: EXISTING CONDITIONS

RIVER ROAD STABILIZATION TOWN OF LINCOLN, VT

0 5 10 20 30 40 50 Feet 1 in = 50 feet AUGUST 31, 2023

(880740 930 STEEP SLOPE TO FORGE -HILL ROAD, APPROX. 1:1.7 APPROX. ELEVATION (FT N 010 000 930 DISCONNECTED RIVER ROAD DISCONNECTED FLOODPLAIN EDGE OF ROAD OVER-STEEP SLOPE -PRONE TO EROSION DRAINAGE SWALE 1.4 APPROX. OHW -EXISTING SEDIMENT BAP 10+00 12+00 11 + 00DISTANCE (FT) Α' А

CROSS SECTION VIEW (LOOKING DOWNSTREAM) - SECTION R-R'



FIGURE 1 - LOOKING DOWNSTREAM



FIGURE 2 - LOOKING UPSTREAM



Statution Statution Statution				
REVISIONS				
TYPICAL SECTION - SECTION A	RIVER ROAD STABILIZATION PROJECT NAME 2	RIVER ROAD LINCOLN, VERMONT		
PROJECT NO. XS-1 SHEET NO.				



SHEET PR-1: PROPOSED CONDITIONS

RIVER ROAD STABILIZATION TOWN OF LINCOLN, VT

0 5 10 20 30 40 50 Feet 1 in = 50 feet AUGUST 31, 2023







	Ŕ	SLR	1 SOUTH MAIN STREET NATREBURY, TO 56:76 80:382335 SLECONSULTING.COM
CONTRACTOR TO ING OF DOWELS AND DRILLING 2 FOOT D DEPEND ON	REVISIONS		
GRADE AT DISCONNECTED JTE ENTRANCE PROPOSED RECONNECTED FLOOD CHUTE ENTRANCE EXISTING GRADE (TYP)) STABILIZATION	DNT
EXISTING LOW FLOW CHANNEL	DELIGIC DESIGNE SCALE A DATE	AS NO UGUST 3 139228.0	LINCOLN, VERMC
	SHEET N	DEI	ſ -1